URBAN PROJECTS
KUWAIT

Preliminary Construction Budget

Varnda published example (960 m², Medium) · 2026-10-11 19:08

1. Executive summary

Complete for the selected scope — Preliminary estimate — not a contractor quotation.

Project name	**Varnda published example (960 m², Medium)**	Total above ground	**960 m²**
Property type	**Private villa**	Construction scope	**Full construction (turnkey)**
Location	**—**	Finishing quality	**Medium**
Plot area	**400 m²**	Estimate level	**Quick estimate**

Estimated construction cost

Low estimate	Typical estimate	High estimate
129,600 KWD	**144,000 KWD**	**163,200 KWD**

Estimated total owner budget

Low estimate	Typical estimate	High estimate
154,040 KWD	**170,600 KWD**	**192,680 KWD**

Price source: Varnda published tier — Medium (VR-02) — Published competitor benchmark · Verified published claim · Low confidence

Important assumptions

- Built-up areas are as entered; plot area is not used as built-up area.
- Percentages are applied to: above-ground base.
- Location and floor height are recorded only; no adjustment coefficient is applied.
- Land cost is excluded.

2. Detailed calculations

Areas by floor

Floor	Area (m²)	Rate (KWD/m²)
Ground floor	320	135 / 150 / 170
First floor	320	135 / 150 / 170
Second floor	320	135 / 150 / 170
Total incl. basement	**960**	

Calculation for each scenario

Item	Scenario	Formula	Amount (KWD)
Construction cost — contractor work			
Above-ground construction Area-rate estimate	Low estimate	960 m² × 135 KWD/m² = 129,600	129,600
	Typical estimate	960 m² × 150 KWD/m² = 144,000	144,000
	High estimate	960 m² × 170 KWD/m² = 163,200	163,200
Owner's additional expenditure			
Design & supervision Percentage	Low estimate	8% × 129,600 (above-ground base) = 10,368	10,368
	Typical estimate	8% × 144,000 (above-ground base) = 11,520	11,520
	High estimate	8% × 163,200 (above-ground base) = 13,056	13,056
Permits & fixed fees Fixed amount	Low estimate = Typical estimate = High estimate	Permits & fees (illustrative) = 5,000	5,000
Contingency reserve Percentage	Low estimate	7% × 129,600 (above-ground base) = 9,072	9,072
	Typical estimate	7% × 144,000 (above-ground base) = 10,080	10,080
	High estimate	7% × 163,200 (above-ground base) = 11,424	11,424

Cost reconciliation

	Low estimate	Typical estimate	High estimate
Construction cost	129,600	144,000	163,200
Owner's additional expenditure	24,440	26,600	29,480
Total owner budget	**154,040**	**170,600**	**192,680**

Construction + owner's additional expenditure = total owner budget (exact, every scenario). Each line is rounded to the nearest KWD; totals are exact sums of rounded lines.

3. Specifications and limitations

What is included

Base-rate inclusions (as published): Turnkey building per m² of built-up area (not plot), as described in the publisher's illustrative tier table.

Medium — Good standard materials and branded fittings.

- Good-standard porcelain flooring
- Quality aluminium systems
- Solid-core internal doors
- Branded sanitary ware
- Standard kitchen allowance
- Quality paint system
- Gypsum ceilings in main rooms
- Paint with partial cladding allowance

What is not included

- Base-rate exclusions (as published): Basement, land, special extras, owner-specific specification. Scope not audited.
- Land cost is excluded.

Selected rate source

Rate used	**Varnda published tier — Medium (VR-02)**
Selected rate	**135 / 150 / 170 KWD/m²**
Source	**Varnda Kuwait (published illustrative tier, S05)**
Source date	**2026-08-06**
Approval status	**Published competitor benchmark**
Evidence status	**Verified published claim**
Evidence confidence	**Low confidence**

Assumptions

- Rate VR-02 is a Published competitor benchmark — not an Urban-approved rate.
- Rate VR-02: Verified published claim — the underlying price evidence has not been verified.

Disclaimer

This is a preliminary planning estimate produced from area-based rates. It is not a contractor quotation, not a priced bill of quantities and not structural design. Final costs depend on approved drawings, site conditions, specifications and tendered prices. Rates marked as published benchmarks are third-party research data, not Urban Projects' approved prices.